


# Top Dry Autoflow Construction Manual 21',24', 33', 36'

**Construction &  
Owner's Manual**

7/30/2002



PNEG-1276





Table of Contents

SAFETY PAGES	4
FOUNDATION REQUIREMENTS	8
HARDWARE	16
SIDEWALL CONSTRUCTION	19
STIFFENER DETAIL	27
C-CHANNEL BRACKET	33
C-CHANNEL	34
CENTER COLLAR	35
RAFTER INSTALLATION	37
PURLIN INSTALLATION	38
DUMP HOPPER INSTALLATION	42
FLOOR SHEET INSTALLATION	43
EAVE FLASHING	44
DUMP CHUTES	46
CABLE PULLEY ASSEMBLY	47
DUMP CHUTE CHAIN ASSEMBLY	48
CENTER CONE ASSEMBLY	50
LEVELING BAND POST INSTALLATION	51
LEVELING BAND INSTALLATION	54
AUTOVENT ASSEMBLY	61
MANWAY COVER ASSEMBLY	63
ROOF ASSEMBLY	64
SAFETY RING INSTALLATION	75
PERFORATED CENTER BAND	77
42" FAN DIFFUSER	78
FAN ENTRANCE SHEETS	80
LOCATION OF PLATFORMS	81
PLATFORM ASSEMBLY	82
TRANSITION ASSEMBLY	88
TOP ACCESS DOOR ASSEMBLY	90
2-RING DOOR INSTALLATION	92
OPTIONAL BIN STEP	95
BASE ANGLE & STIFFENER SHIMS	96
WARRANTY	98

# SAFETY GUIDELINES

This manual contains information that is important for you, the owner/operator, to know and understand. This information relates to protecting **personal safety** and **preventing equipment problems**. It is the responsibility of the owner/operator to inform anyone operating or working in the area of this equipment of these safety guidelines. To help you recognize this information, we use the symbols that are defined below.

Please read the manual and pay attention to these sections. Failure to read this manual and it's safety instructions is a misuse of the equipment and may lead to serious injury or death.



This is the safety alert symbol. It is used to alert you to potential personal injury hazards. Obey all safety messages that follow this symbol to avoid possible injury or death.



**DANGER**

**DANGER** indicates an imminently hazardous situation which, if not avoided, will result in death or serious injury.



**WARNING**

**WARNING** indicates a potentially hazardous situation which, if not avoided, could result in death or serious injury.



**CAUTION**

**CAUTION** indicates a potentially hazardous situation which, if not avoided, may result in minor or moderate injury.


**CAUTION**

**CAUTION** used without the safety alert symbol indicates a potentially hazardous situation which, if not avoided, may result in property damage.

**NOTE**

**NOTE** indicates information about the equipment that you should pay special attention to.

**CAUTION!**



Excessive vacuum or internal pressure from fans or other air moving systems can cause roof damage. Make sure all roof vents are operating properly. Shut roof down when conditions could cause roof vent to freeze.

GSID DOES NOT WARRANT ANY ROOF DAMAGE CAUSED BY EXCESSIVE VACUUM OR INTERNAL PRESSURE FROM FANS OR OTHER AIR MOVING SYSTEMS. ADEQUATE VENTILATION AND/OR "MAKEUP AIR" DEVICES SHOULD BE PROVIDED FOR ALL POWERED AIR HANDLING SYSTEMS. GSID DOES NOT RECOMMEND THE USE OF DOWNWARD FLOW SYSTEMS (SUCTION). SEVERE ROOF DAMAGE CAN RESULT FROM ANY BLOCKAGE OF AIR PASSAGES. RUNNING FANS DURING HIGH HUMIDITY/COLD WEATHER CONDITIONS CAN CAUSE AIR EXHAUST OR INTAKE PORTS TO FREEZE.

ATTENTION: The decal shown below should be present on the inside of the door cover of the two ring, 24" porthole door cover and the roof manway cover.

Grain Systems  
1004 East Illinois Street  
Assumption, IL 62510-0020  
(217) 226-4421



**Keep clear of all augers.  
DO NOT ENTER this bin!**

**If you must enter this bin:**

- 1. Shut off and lock out all power.**
- 2. Use safety harness and safety line.**
- 3. Station another person outside the bin.**
- 4. Avoid the center of the bin.**
- 5. Wear proper breathing equipment or respirator.**

**Failure to heed these  
warnings will result in  
serious injury or death**

ATTENTION: The decal shown below should be present on the outside of the door cover of the two ring, 24" porthole door cover and the roof manway cover.

Grain Systems  
1004 East Illinois Street  
Assumption, IL 62510-0020  
(217) 226-4421



# CAUTION



## DON'T



## DO

**UNLOADING INSTRUCTIONS:**

1. Use **CENTER OUTLET ONLY** until **NO** grain remains above this outlet.
2. Side outlets to be used **ONLY** when above condition is satisfied.
3. Lock all side outlets to avoid accidental premature use.

---

**Failure to follow proper unloading practices will result in structural damage or collapse of tank.**

DC-586

**Foundation Requirements  
for  
Top Dry Bins  
(4.00" "Top Dry" BIN CORRUGATION)**

**1. REQUIREMENTS:**

The following foundation recommendations are a revision to earlier manuals distributed by The GSI Group, Inc.


**Note: There are changes in foundation dimensions from past publications. These dimensions are critical to the proper installation and function of each foundation.**

**2. SELECTING THE PROPER SITE:**

The selected site should be level, firm, and free from underlying debris. The bin can be installed satisfactorily on slopes, but as the slope increases, additional labor and materials are required for the foundation. The concrete foundation surface must be level. If some fill is required, it should be watered and tamped thoroughly to prevent uneven settling from the weight of the bin. Naturally, the site must allow convenient access for easy loading and unloading, plus provide additional space for future units. Also consider the positioning of handling equipment, availability of electricity, and the placement of fans, heaters, and gas tanks.

**3. SCRIBE THE DIAMETER**


Having determined the center of the site, drive a small 2 x 4 in the ground to mark the center point of the foundation. The top of the stake should be the same height as the finished foundation will be. Using one large spike, nail a straight 2 x 4 (approximately 2 ft. longer than the radius of the bin) to the top of the center spike. The swiveling 2 x 4 will act as a compass, enabling you to scribe the correct diameter of your foundation and later locate the anchor and stiffener bolt locations. (Note: Making the 2 x 4 two feet longer than the radius allow the 2 x 4 to also be used as a leveling device and for pulling concrete).





#### 4. PREPARE THE FOUNDATION FORMS


Having scribed the diameter of your foundation, proceed by digging the foundation's footing. This consist of a large circular trench dug inside the foundation line, (Refer to foundation details for necessary information). Once the footing has been dug, you are ready to build the forms. It is important that your forms be rigid enough to hold its shape against the poured concrete. Also, the foundation must be flat. Sloped floors cannot be used in drying bins. A carpenter's level placed on top of your compass 2 x 4 will enable you to set the top of the forms to match the top of the center stake. Check the form work with a transit to insure a uniform elevation for the entire foundation. The foundation should be level within 1/8" on non-stiffened tanks and 1/4" on stiffened tanks at bin wall perimeter. Stiffened tanks must be shimmed level.



All foundation specifications shall be construed as recommendations only. Because of the many variable conditions in actual installation, The GSI Group, Inc. assumes no liability for results arising from the use of such recommendations.

#### (ALTERNATE FOUNDATION FORMS)

There are two styles of foundation forms commonly used. The first is the circular form shown on the previous page. The second style of foundation can be made of 2" x 8" boards set into a square with the corners blocked off to form an octagon. This eight sided form will approximate a circle and can also be constructed easily.

**Second style of foundation**

***\* All concrete to have a minimum compressive strength of 3,000 psi @ 28 days.***

**5. PLACE THE REINFORCEMENT**

Once the forms and trench have been prepared, begin the placement of reinforcement rods at various levels in your foundation's footing. See the appropriate charts and drawings for your bin to determine requirements and positions of the reinforcement. The reinforcement rods offer their greatest strength when lapped properly and connected by wiring or welding. Next, place a minimum of 2" of compacted sand on the inside section of the foundation to provide a good base for the concrete and protect against rodents. The sand should then be covered with 4 mil polyethylene plastic which will act as a moisture barrier. Two layers of 6 x 6 wire mesh should then be added to the entire area of the foundation to complete your preparation of the bin's foundation.

## INLINE CENTRIFUGAL FAN PAD

### 6. PLACEMENT OF THE FAN PAD: G.S.I TRANSITIONS / FANS ONLY.

If a fan is to be installed, refer to the following diagram to determine the concrete pad size.

The top of this pad should be level with the top of the bin's foundation.


Recommended pad thickness is 4" minimum.

Front of pad should be perpendicular to bin wall.

Pad for heater not required.

#### IMPORTANT!

FAN PAD AND FAN MUST BE LEVEL AND SMOOTH FOR PROPER OPERATION.  
VIBRATION PROBLEMS CAN RESULT FROM IMPROPER FAN LEVELING.



**TR-4734**

A=22" for fans without heaters

**TR-7048**

A=48" for fans without heaters

## DUCT & DRYING FAN PAD OPTIONAL


### 7. PLACEMENT OF THE DUCT FAN PAD: G.S.I TOP DRY DUCT SYSTEM ONLY.

Refer to the following diagram to determine the duct pad size.

The top of this pad should be level with the top of the bin's foundation.

Recommended pad thickness is 4" minimum.

Front of pad should be perpendicular to bin wall.




### Anchor Bolt Placement

Having poured and leveled the concrete, use the center stake and straight 2 x 4 again to find the bolt circle radius for the outside hold down brackets. Select a starting point and stretch a premeasured chord along the imaginary circle formed by the bolt circle radius. Take into consideration the placement of these bolts so as not to interfere with the positions of bin doors and transitions. (Refer to the following chart for necessary radii and chord lengths.) Take your time and work carefully since accuracy is important.

**NOTE:** Top edge of slab where the bin wall sets must be held to within 1/8" of level.


Bin Dia	"B" Bolt Circle Radius	No. of Anchors	"E" Chord Distance
12'	6'-3.1/4"	8	4'-9.9/16"
15'	7'-9.1/8"	10	4'-9.9/16"
18'	9'-3.1/16"	12	4'-9.1/2"
21'	10'-8.15/16"	14	4'-9.3/8"
24'	12'-2.7/8"	16	4'-9.5/16"
27'	13'-8.3/4"	18	4'-9.1/4"
30'	15'-2.11/16"	20	4'-9.1/8"
33'	16'-8.9/16"	22	4'-9.1/16"
36'	18'-2.1/2"	24	4'-9.1/16"
42'	21'-2.5/16"	28	4'-8.15/16"
48'	24'-2.1/8"	32	4'-8.7/8"
54'	27'-1.15/16"	36	4'-8.13/16"
60'	30'-1.3/4"	40	4'-8.3/4"



## FROST FREE PAD (TOPDRY BINS)

### Notes:

1. Foundation site should be well drained and free of vegetation or debris.
2. Foundation design is based on a minimum soil bearing capacity of 3000 psf.  
If soil bearing capacity is in doubt, contact a local soil testing engineer.
3. Concrete shall have a minimum compressive strength of 3000 psi at 28 days.
4. Requirements for reinforcement do not include overlap.
5. Lap all circumferential bars 35 bar diameters and stagger all laps in plan 3'-0".
6. All material used for backfill inside the ring wall should be clean, well graded, crushed stone or sand-gravel mixture. Backfill should be placed in 6" lifts and well compacted.
7. The optional #4 rebar grid can be substituted for the wire mesh in most cases.  
Place the #4 bars in the pad in an 18" x 18" grid.



\* Contact GSI Engineering for heights greater than 6".

## FROST FREE FOUNDATION TOP DRY BINS

Diameter of Bin: 21'  
Corrugation: 4.00"

Ring No.	B	N	OutSide Radius	Sq. Ft. Mesh 6x6 -6/6	Optional #4 18"x18"Grid(ft.)	Length #6 Bar (ft.)	Total Cu.Yds. Concrete
6	1 ft. 1 in.	2	11 ft. 3 in.	700	500	200	11
7,8	1 ft. 7 in.	2	11 ft. 3 in.	700	500	200	12

Diameter of Bin: 24'  
Corrugation: 4.00"

Ring No.	B	N	Outside Radius	Sq. Ft. Mesh 6x6-6/6	Optional #4 18"x18" Grid (ft.)	Length #6 Bar (ft.)	Total Cu. Yds. Concrete
6	1 ft. 1 in.	2	12 ft. 9 in.	900	600	200	13
7,8	1 ft. 9 in.	2	12 ft. 9 in.	900	600	200	15
9,10	2 ft. 6 in.	3	13 ft. 2 in.	900	600	400	18

Diameter of Bin: 30'  
Corrugation: 4.00"


Ring No.	B	N	Outside Radius	Sq. Ft. Mesh 6x6-6/6	Optional #4 18"x18" Grid (ft.)	Length #6 Bar (ft.)	Total Cu. Yds. Concrete
6	1 ft. 2 in.	2	15 ft. 9 in.	1400	900	200	19
7,8	1 ft. 10 in.	2	15 ft. 10 in.	1400	900	200	21
9,10	2 ft. 8 in.	3	16 ft. 1 in.	1400	900	500	25
11	3 ft. 8 in.	4	16 ft. 5 in.	1400	900	700	29

Diameter of Bin: 36'  
Corrugation: 4.00"

Ring No.	B	N	Outside Radius	Sq. Ft. Mesh 6x6-6/6	Optional #4 18"x18" Grid (ft.)	Length #6 Bar (ft.)	Total Cu. Yds. Concrete
6	1 ft. 3 in.	2	18 ft. 9 in.	2000	1300	300	26
7,8	2 ft. 0 in.	2	18 ft. 11 in.	2000	1300	400	30
9,10	2 ft. 10 in.	3	19 ft. 0 in.	2000	1300	600	33
11,12	3 ft. 11 in.	4	19 ft. 6 in.	2000	1300	900	39


### Hardware/Bolting Requirements

- Grade 2 bolts are designated with a plain head.




**Grade 2**

- Grade 5 bolts are designated by 3 slash marks on the head. All 5/16" diameter bolts are to be Grade 5 or higher.



**Grade 5**

- Grade 8 bolts are designated by 6 slash marks on the head.



**Grade 8**

- Grade 8.2 bolts are designated by 6 slash marks on the head in a sunrise pattern. All 3/8" diameter bolts are to be Grade 8 or 8.2.



**Grade 8.2**


**IMPORTANT: Do not tighten bolts to exceed the torque specifications listed below.**

### Important Hardware Usage

- 20 gauge through 15 gauge sidewall sheets, use 5/16" x 3/4" bolts and nuts. (S-275)
- 14 gauge and 13 gauge sidewall sheets, use 5/16" x 3/4" bolts and nuts. (S-275)
- Use 5/16" x 1 1/4" (S-277) for attaching floor flashing to the sidewall.


BOLT SIZE	TORQUE (ft. lb.)	
	MINIMUM	MAXIMUM
5/16" - 18	15	20
3/8" - 16	35	42
7/16" - 14	65	72
1/2" - 13	95	105

**CAUTION: UNDER NO CONDITION SHALL ANY OTHER BOLTS BE SUBSTITUTED FOR THOSE SUPPLIED BY GRAIN SYSTEMS, INC.**






**REFER TO TOP DRY TANK BOLTING REQUIREMENTS  
FOR COMPLETE BOLT USAGE**



**SIDE  
VIEW**


**S-275**

.3125" x .750" pre-assembled with a steel backed neoprene washer.



**GRADE 5  
TOP VIEW**


This bolt is used to connect horizontal and vertical seams for 13 gage and thinner sidewall sheets to each other, and to bolt the stiffeners to the sidewall sheets. It is also used in attaching roof panels to the top sidewall sheet and attaching roof panels and flashing to the center collar.



**SIDE  
VIEW**

**S-277**


.3125" x 1.250" pre-assembled with a steel backed neoprene washer.




**GRADE 5  
TOP VIEW**

This bolt is primarily used to connect roof panels together where they overlap. It is also used at the bottom of the flat bottomed bins to attach the base angle to the sidewall sheet. A small number of these are provided for joints and FC-42076 splice plates for the stiffeners to sidewall connection.


**REFER TO TOP DRY TANK BOLTING REQUIREMENTS  
FOR COMPLETE BOLT USAGE**



**SIDE  
VIEW**



**GRADE 8**




**GRADE 8.2**

**TOP VIEW**


**S-7927**

.375" x 1.000" hex flanged head **without** a plastic sealing washer.


This bolt is used to splice the stiffeners together on the flanges. A steel flat washer is used on the nut side of the connection. They are also used on "c" channel splices and mounting "c" channel to wall bracket.



**SIDE  
VIEW**



**GRADE 8**



**GRADE 8.2**

**TOP VIEW**

**S-7928**

.375" x 1.500" hex flanged head **without** a plastic sealing washer.


This bolt is used to attach the wall bracket to the sidewall and stiffener. A steel flat washer is used on the nut side of the connection.

Note: The only washers shipped loose with the bins are the steel flat washers. The 5/16" steel flat washer (S-845) is used where the base angle attaches to the sheet and some are used at the main eave clips. The 3/8" steel flat washers (S-248) are used at the stiffener splices and some are used in the roof rafter splices.


### LOCATION OF ACCESSORIES

Below is a typical Top Dry bin layout showing suggested locations of Top Dry Accessories. When locating the manway be sure the outside ladder will not interfere with other accessories below. Roof vents should be spaced evenly around the roof. (Quantity will vary with individual systems.)

**NOTE:** The Top Dry system should be provided with a dependable equipment ground.



# VERY IMPORTANT!



**All 4.00" corrugated sidewall sheets must be placed correctly.**

**All 4.00" corrugated sidewall sheets have a top and bottom!**

**Failure to observe this will not allow the door to fit properly.**

**Carefully review the erection manual and place sidewall sheets as shown.**

## SIDEWALL GAUGES

TANK DIA. (FT.)	NUMBER OF RINGS OF SIDEWALL	Sidew all Base Ring	Sidew all Ring #2	Sidew all Ring #3	Sidew all Ring #4	Sidew all Ring #5	Sidew all Ring #6	Sidew all Ring #7	Sidew all Ring #8	Sidew all Ring #9	Sidew all Ring #10	Sidew all Ring #11
21	5	20ga	20ga	20ga	20ga	20ga						
21	6	20ga	20ga	20ga	20ga	20ga	20ga					
21	7	20ga	20ga	20ga	20ga	20ga	20ga	20ga				
21	8	18ga	20ga	20ga	20ga	20ga	20ga	20ga	20ga			
24	5	20ga	20ga	20ga	20ga	20ga						
24	6	20ga	20ga	20ga	20ga	20ga	20ga					
24	7	18ga	20ga	20ga	20ga	20ga	20ga	20ga				
24	8	18ga	18ga	20ga	20ga	20ga	20ga	20ga	20ga			
24	9	17ga	18ga	18ga	20ga	20ga	20ga	20ga	20ga	20ga		
24	10	17ga	17ga	18ga	18ga	18ga	20ga	20ga	20ga	20ga	20ga	
30	5	18ga	18ga	18ga	18ga	20ga						
30	6	18ga	18ga	18ga	18ga	18ga	20ga					
30	7	17ga	18ga	18ga	18ga	18ga	18ga	20ga				
30	8	17ga	17ga	18ga	18ga	18ga	18ga	18ga	20ga			
30	9	17ga	17ga	17ga	18ga	18ga	18ga	18ga	18ga	20ga		
30	10	16ga	17ga	17ga	17ga	18ga	18ga	18ga	18ga	18ga	20ga	
30	11	16ga	17ga	17ga	17ga	17ga	18ga	18ga	18ga	18ga	18ga	20ga
36	5	17ga	18ga	18ga	18ga	20ga						
36	6	17ga	18ga	18ga	18ga	18ga	20ga					
36	7	16ga	17ga	18ga	18ga	18ga	18ga	20ga				
36	8	16ga	16ga	17ga	18ga	18ga	18ga	18ga	20ga			
36	9	16ga	16ga	16ga	17ga	18ga	18ga	18ga	18ga	20ga		
36	10	15ga	16ga	16ga	16ga	17ga	18ga	18ga	18ga	18ga	20ga	
36	11	14ga	15ga	15ga	16ga	16ga	17ga	18ga	18ga	18ga	18ga	20ga


**NOTE: Fan Entrance sheets and Plenum Access door sheets are located in the second ring from the top of the bin, just below the upper drying floor.**

## SIDEWALL ERECTION INSTRUCTIONS

Before bolting the sidewall sheets together, check that you have the proper gauge steel for the first ring. The higher gauge numbers denote the thinner materials. (For example, 22 gauge material is thinner than 14 gauge.) In erecting most grain bins the thinnest material usually goes on top, therefore the first sidewall ring you assemble will be the top ring of your bin. Check the various gauges of your bin with the Color Code Chart and begin building accordingly. REMEMBER.....Assemble the top ring first.

GAUGE	COLOR CODE
22	WHITE
20	RED
19	BLACK/YELLOW
18	ORANGE
17	PINK/LIGHT BLUE
16	BLUE
15	BROWN/RED
14	GREEN
13	YELLOW/BLUE
12	BLACK
11	PINK
10	LIGHT BLUE
9	BLUE/ORANGE
8	YELLOW

Once you have selected the proper gauge material, begin assembling all sidewall sheets in the following manner: Standing on the inside the bin, place the left panel to the inside with the right panel to the outside. (See Fig. A-A). **Check to see that the sidewall sheet is "Right Side up" reference page 28 for details.**



**FIG. A-A**


## Top Dry Autoflow

---

After assembling the **second ring**, lift the top ring sheets in place, add top stiffeners, build the Top Dry floor, then the roof.


Note: The sidewall sheets used for the **top ring** are punched to accommodate the eave flashing bolts.

**Note:** The fan entrance sheet and access door are located in the second ring. Attach the top stiffeners, leaving out the (7) bolts indicated in Figure #15 at each stiffener location. Install the flashing bolts from the outside and tighten first nut on the inside of the bin.



## CAULKING DETAIL

*Note: The rope caulking is installed before each sheet is assembled. Apply rope caulking between the last vertical row of bolts and edge of outside sheet. There is sufficient caulking for all vertical seams on storage and drying bins. Wipe sheet clean where caulking is to be applied.*




**Standard Sidewall Sheets  
As Viewed From Inside**

Using correct size bin bolts throughout, begin assembling sidewall sheets end to end (overlapping the same way throughout) until the ring is completed. All body sheet bolts are to be installed with the bolt head and its neoprene washer to the outside, and the nut on the inside. Do not tighten bolts until all sheets are assembled and form a complete ring. Attach lifting brackets to stiffener bolt holes. These straps, coupled to the jacks will enable you to later elevate your bin. Now tighten the bolts in sequence, starting from the center and working to the edge in both directions. This permits the sidewall sheets to draw-up evenly. Complete one ring and stop. You are now ready to assemble the roof. Refer to the roof erection manual for roof assembly instructions located in roof hardware box.



### LIFTING JACKS & BRACKETS

**NOTE:** The number of lifting jacks required is best determined by personal experience. Factors such as bin size, soil compaction, wind velocity, jack design, etc., are all to be considered when deciding how many to use. If in doubt, use one jack on every other stiffener. GSI recommends heavy duty jacks rated at 6,000 lbs. or more.




### Lifting Jack Usage

Give some thought before starting your bin on location of door and other accessories. Proper placement of lifting jacks in relationship to anchor bolts could make a difference on odd or even ring bins. Walk-thru door is centered between two stiffener anchor bolts. The sidewall sheets are also staggered 1/2 from end to end.

#### **WARNING!!**

**The number of lifting jacks required is best determined by personal experience. Factors such as bin size, soil compaction, wind velocity, jack design, etc. are all to be considered when deciding how many to use. If in doubt, use one jack on every vertical seam. Be sure to use Heavy Duty jacks for commercial installation.**



Lifting brackets should be attached to the stiffeners. Normally you will need to attach to at least 4 bolts per stiffener. Anchor all jacks securely with metal stakes and cable. Now raise the bin just high enough to assemble the next ring. When lifting your bin, crank all jacks at an equal rate. This will prevent bowing previously assembled rings and make for easier hole alignment. To the inside of the first ring, bolt the next ring. Be sure to stagger the sheets and select the proper gauge material. Lower the bin on the foundation after assembling and tightening bolts on the new ring or rings. When installing Duct Work for the drying fans be sure to install it as you go up with the bin letting the duct set on the foundation before the bolts are tightened to assure proper alignment. Now rebolt the lifting straps to the lowest ring in place thus far. Continue ring additions until you are ready for door installation. You may want to leave sheets loose to make the attachment of the stiffeners easier.

#### **NOTES:**

*- Add inside and outside ladders to binwalls as you continue to raise the bin.*

## STIFFENER GAUGES

NOMINAL DIA. OF SIDEWALL (Ft)	NUMBER OF RINGS OF SIDEWALL	Stiffener Base Ring	Stiffener Ring #2	Stiffener Ring #3	Stiffener Ring #4	Stiffener Ring #5	Stiffener Ring #6	Stiffener Ring #7	Stiffener Ring #8	Stiffener Ring #9	Stiffener Ring #10	Stiffener Ring #11
21	5		14ga	16ga	16ga	16ga						
21	6		14ga		16ga	16ga	16ga					
21	7		12ga		14ga	16ga	16ga	16ga				
21	8		12ga		14ga		16ga	16ga	16ga			
24	5		14ga	16ga	16ga	16ga						
24	6		12ga		14ga	16ga	16ga					
24	7		12ga		14ga	16ga	16ga	16ga				
24	8		12ga		14ga		12ga	16ga	16ga			
24	9		10ga		12ga		12ga	14ga	14ga	16ga		
24	10		8ga		10ga		12ga		14ga	16ga	16ga	
30	5		12ga	14ga	16ga	16ga						
30	6		12ga		14ga	16ga	16ga					
30	7		12ga		12ga	14ga	16ga	16ga				
30	8		10ga		12ga		14ga	16ga	16ga			
30	9		10ga		12ga		12ga	14ga	16ga	16ga		
30	10		8ga		10ga		12ga		14ga	16ga	16ga	
30	11		8ga		10ga		12ga		12ga	14ga	16ga	16ga
36	5		12ga	14ga	16ga	16ga						
36	6		12ga		12ga	14ga	16ga					
36	7		10ga		12ga	14ga	14ga	16ga				
36	8		10ga		12ga		12ga	14ga	16ga			
36	9		8ga		10ga		12ga	14ga	14ga	16ga		
36	10		8ga		10ga		12ga		12ga	14ga	16ga	
36	11		8ga		8ga		10ga		12ga	14ga	14ga	16ga



**NOTE: All Top Dry Bin Stiffeners are mounted on the outside of the bin. See Stiffener instructions for stiffener joint details and stiffener to sidewall attachment.**

## OUTSIDE STIFFENERS

- The XX in the part numbers at the bottom will identify the Stiffener's gauge.

Example: FC-4205714 is a 2-Ring Standard Stiffener 14 Gauge


Stiffener Description	Part No.	Overall Length	Color Code
2-Ring 10 Ga. (Base)	FC-4207210	94 27/32"	White
2-Ring 12 Ga. (Base)	FC-4207212	94 27/32"	Black
2-Ring 14 Ga. (Base)	FC-4207214	94 27/32"	Green
2-Ring 16 Ga. (Base)	FC-4207216	93 13/16"	Blue
2-Ring 8 Ga. (Base)	FC-4207308	88 3/16"	Yellow
2-Ring 8 Ga.	FC-4206308	87 15/16"	Yellow
2-Ring 10 Ga. Trans.	FC-42062	94 19/32"	Purple
2-Ring 12 Ga.	FC-4205712	94 19/32"	Black
2-Ring 14 Ga.	FC-4205714	94 19/32"	Green
2-Ring 16 Ga.	FC-4207516	93 9/16"	Blue
2-Ring 18 Ga.	FC-4207518	93 9/16"	Orange
2-Ring 16 Ga. Top	FC-4206516	85 9/16"	Blue
2-Ring 18 Ga. Top	FC-4206518	85 9/16"	Orange
1-Ring 12 Ga.	FC-4205912	50 19/32"	Black
1-Ring 14 Ga.	FC-4205914	50 19/32"	Green
1-Ring 16 Ga.	FC-4207416	49 9/16"	Blue
1-Ring 18 Ga.	FC-4207418	49 9/16"	Orange
1-Ring Top 16 Ga.	FC-4206616	41 7/16"	Blue
1-Ring Top 18 Ga.	FC-4206618	41 7/16"	Orange
Splice	FC-42076	10 11/16"	---



### TOP STIFFENER STARTING LOCATION

Refer to Figure #10, for proper location of top stiffeners. On the overlap of the stiffeners, and on the splice, use 3/8" x 1" hex bolts, a washer on thee nut side connection. Refer to the stiffener layout, Figure #8, for stiffener usage.


All stiffeners are outside the bin wall. Use 5/16" x 3/4" Grade 5 bin bolts with head and neoprene washer to the inside of the bin wall. Refer to proper charts and illustrations on the previous two pages for proper location of stiffeners and sidewall sheets.




## STIFFENER INSTALLATION & LOCATION

When installing bottom stiffeners, you may find that in some cases the stiffener with base plate attached will not rest on the foundation (due to unlevel concrete, etc.) Shim plates have been furnished and should be used to fill opening between base plate and concrete.


**IMPORTANT:** If shim plates are not used where required, the downward pressure of the stiffeners will not be transferred directly to the foundation, and bin failure could result.



**SPLICE PLATE JOINT  
(TOP VIEW)**



**OFFSET JOINT CONNECTION  
DETAIL**



## BOLTING REQUIREMENTS

•


### 2 STIFFENERS PER SIDEWALL SHEET

Sidewall Gauge	Horizontal Seam	Vertical Seam	Stiffener To Sidewall	Overlap Seam
17 Thru 20	5/16" x 3/4" [10]	5/16" x 3/4" [42]	5/16" x 3/4" [20]	5/16" x 3/4" [2]


All bolts are standard bin bolts with neoprene washers. For horizontal and vertical seam bolts, the bolt head and neoprene washers are on the outside of the bin.

Note: For the splice plates FC-42076 use 5/16" x 1.1/4" bolts for the stiffener to sidewall connections.

#### Standard (17 Gauge Thru 20 Gauge) Sheet Bolting Detail (Viewed from outside of the bin)



STIFFENER & SEAM LOCATIONS




2 stiffeners per sidewall sheet  
Top Dry stiffener starting location -18' to 36'  
4" corrugation stiffener only



### STIFFENER TO C-CHANNEL BRACKET INSTALLATION

Install the stiffeners on the outside of the bin (as shown below) and the wall brackets on the inside of the bin. The wall brackets are to be positioned with the bracket's top hole matching the first hole up from the horizontal seam (not counting the horizontal seam). Bracket to sidewall connection using a 3/8" x 1.1/2" bolt (S-2086), head outside, with a neoprene washer (S-3558) against the wall on the inside.





"C" CHANNEL INSTALLATION

Fasten the rolled "C" eave members to the wall brackets in the upper 2 holes of the top set of three (3) holes leaving the bolts loose.

Install the splice plates at the rolled "C" eave member seams using 3/8" x 1" flanged hex bolts and nuts. Tighten all bolts.


"C" Channel Attachment.



NOMINAL DIA. OF TANK (FT.)	PART "A" NUMBER
21'	TD-100772
24'	TD-100678
30'	TD-100643
36'	TD-100731


**CENTER COLLAR ASSEMBLY**

Add channel braces and brace plates to center collar as shown using 3/8" x 1" bolts and nuts. (Do not attach cross channel until floor is done.)



NOMINAL DIA. OF TANK (FT.)	PART "A" NUMBER
21'	TD-100631
24'	TD-100632
30'	TD-100634
36'	TD-100730


Position the center collar at the center of the bin and raise it to the required height per diameter of tank. Height is measured form the bottom of the center collar to the concrete.



NOMINAL DIA. OF TANK (FT.)	DIMESNION "A"
21'	8'-0.1/2"
24'	8'-9.1/2"
30'	10'-5.3/16"
36'	11'-8.3/4"

### RAFTER INSTALLATION & FLOOR SUPPORT ANGLE ATTACHMENT

When installing the rafters, set the lower clip end on the "C" eave member. Leave the bolts to the center collar and the eave member loose until all rafters are in place. Use 3/8" x 1" hex bolts and nuts to connect the center collar and eave member to three (3) rafters at 90 degrees to each other. These first three (3) rafters should all face the same direction. Every other rafter should alternate direction. **IMPORTANT:** There are left & right rafters. Be sure to alternate left, right, left, right, etc.. The floor sheet support purlins can now be installed using 5/16" x 3/4" bin bolts. There are two (2) different lengths of purlins to fit between the rafters. Insert the straight tab of the purlin through the upper slot in the left hand rafter when looking toward the bottom of the rafters. Bolt the bent end of the purlin to the right hand rafter in the upper two (2) holes. After inserting the next purlin tab, bolt the first purlin tab to the second purlin. Continue around the bin alternating lengths as the rafter facings did. Tighten all bolts.




**Floor Support Angle Assembly**

NOMINAL DIA. OF TANK (FT.)	LONG SUPPORT	SHORT SUPPORT
21'	TD-100777	TD-100778
24'	TD-100720	TD-100721
30'	TD-100650	TD-100651
36'	TD-100740	TD-100741


## 21' SPECIAL ANGLE PURLIN ASSEMBLY

Where two rafters face the same direction use 5/16" x 3/4" bin bolts and nuts with the three bent edges facing toward the sidewall, the longest edge on top.





## 21' INTERMEDIATE PURLIN

Bolt purlins to rafters (as shown in the photo) in the 4th hole counting up from the sidewall.



### 24' INTERMEDIATE PURLIN



Counting up from the lower end of the rafter, on the underneath side, the angle purlins bolt in the 3rd hole using 5/16" x 3/4" bin bolts. The angle is to be bolted to the underneath side of the rafters, joining rafter to rafter, with the angle interior angle facing the center of the bin. (as shown in the photo). Tighten all bolts.



The angle is to be bolted on the underneath side of the rafters, joining rafter to rafter, with the angles interior angle facing the center of the bin.

### 30' INTERMEDIATE PURLIN

The upper purlins are bolted using 5/16" x 1-1/4" bolts in the 9th hole counting up from the sidewall. The middle pulins are bolted in the 4th hole counting up from the sidewall. Bolt purlins to rafters with interior angle facing the center of the bin as shown in the photo.




The angle is to be bolted on the underneath side of the rafters, joining rafter to rafter, with the angles interior angle facing the center of the bin.




### 36' INTERMEDIATE PURLIN

The upper purlins are bolted using 5/16" x 1-1/4" bolts in the 9th hole counting up from the sidewall. The middle pulins are bolted in the 4th hole counting up from the sidewall. Bolt purlins to rafters with interior angle facing the center of the bin as shown in the photo.




The angle is to be bolted on the underneath side of the rafters, joining rafter to rafter, with the angles interior angle facing the center of the bin.




## DUMP HOPPER INSTALLATION

Pre-assemble the dump hoppers, dump brackets, and flashing angles to the floor sheets. Place a dump hopper under the floor sheet and align it with the pre-punched large hole. Place a flashing angle on top of the sheet across the outer edge of the hopper entrance with the interior of the angle facing the sidewall. Screw down through the angle, sheet, and hopper with 5/16" x 3/4" self-tapping screws.



## FLOOR SHEET INSTALLATION




The assembled sheets can now be laced over the framework. as the sheets are placed and overlapped they are to be screwed down to the rafters using 5/16" x 3/4" self-tapping screws. There are certain holes in the sheets that should not be screwed down at this time to mount leveling band posts later. See chart below. all holes are counted from the sidewall sheet upto the center of the bin.

NOMINAL DIA. OF TANK (FT.)	NUMBER OF HOLES TO LEAVE EMPTY
21'	3RD, AND 8TH HOLES
24'	3RD, AND 8TH HOLES
30'	4TH, 7TH, AND 10TH HOLES
36'	3RD, 6TH, 10TH, AND 12TH HOLES

## FLASHING BOLT INSTALLATION


Install the eave flashing bolts (5/16" x 1.1/4") through the sidewall and tighten first nut. **Note at the vertical sidewall seams, one bolt is turned around to avoid interference with eave flashing (refer to photo).**

Left bolt on the each vertical sidewall seam level with the eave flashing bolts (as viewed from inside the bin) is to be installed bolt in, nut out, as shown in the photo to the right.




## EAVE FLASHING INSTALLATION


Install the eave flashing centered on the floor sheet (1 per) with the bent edge towards the sidewall install a fender washer (S-3671) and nut. Screw the flashing to the flashing angle at the dump hopper opening with (5) #10 (S-280) screws and screw the flashing pieces together where they overlap with (3) #10 self drilling (S-280) screws.



#10 Self-Drilling  
Screws (S-280)




Floor Flashing Angle  
(TD-100654)




**Flashing Attachment.** 1) Sidewall, 2) Flashing TD-100648, 3) Floor sheet, 4) 5/16" x 1.1/4" bin bolt. Note that there is a nut in between the sidewall sheet and the flashing sheet.

## EAVE FLASHING INSTALLATION




### EAVE FLASHING SPLICE

The flashing splice pieces can now be attached to the eave flashing to seal around the rib of the floor sheet as shown with (S-280) #10 self-drilling screws.




## OUTER DUMP CHUTES

Bolt a TD-100598 angle dam to each dump chute using (3) 1/4" x 5/8" bolts and nuts, as shown below. Use 1/4" x 5/8" bolts and double nuts to fasten dump chutes to hopper. **Do not tighten first nut down.** Lock second nut to first nut and **make sure chutes raise and lower FREELY!**




### PULLEY ASSEMBLY

Position the pulley assembly to the cross angle in the middle of the center collar assembly. Use a 3/8" x 1" hex head cap bolt to fasten assembly to the cross angle. Position the pulley in the direction of the desired winch location on the sidewall.




Field drill (5) 3/8" diameter holes as shown at left. Attach the pulley assembly with 5/16" x 3/4" bolts with the neoprene on the inside of the bin.



## DUMP CHUTE CHAIN ASSEMBLY





Attach all dump chute chains directly to the lift(TD-100801) plate as shown in diagram below.

Install all chains using "S" hooks (S-4692) to attach the chains to the dump chutes and lift plates. Keep excess chain at the lift plate. Adjust the chains until the chutes are approximately level when the lift plate is in the closed (up) position. Once the chains are uniformly adjusted, crimp the "S" hooks closed. Check when attaching the "S" hook to the end link on a chain that the end has not been cut open. If this is found remove the end link or shift up and use the next link in chain. The lift plate should be approximately 12" down from the cross channel when the chutes are level.




Crimp "S" hooks after final chute adjustment

Chain leading to outer chutes





## DUMP CHUTE CHAIN ASSEMBLY




Chutes in closed position




## CENTER CONE ASSEMBLY

Bolt the sections together to form perforated cone as shown below. Use 1/4" x 5/8" bolts and nuts to attach sections together.


**Flat Overhead View**



**Formed Overhead View**




**Side Formed View**



## CENTER CONE INSTALLATION


After chains have been adjusted, install cone over the center collar. Fasten Cone Assembly with (12) #10 x 3/4" self-drilling screws (S-280).



### 21' & 24' LEVELING BAND POST INSTALLATION

Install the leveling band posts on the floor as shown.

The third and eighth holes in the floor sheet indicate the location of the leveling band posts. Attach posts with 5/16" x 1.1/4" bin bolts (S-277). The third hole from the bottom of the sheet, there will be 7 posts (1 every third sheet, except the last bay will cover five sheets). In the eighth hole there will be 5 posts (1 every fourth sheet). After all of the posts have been installed fill the unused holes with 5/16" x 1.1/4" bin bolts.




---

## 30' LEVELING BAND POST INSTALLATION

Install the leveling band posts on the floor as shown in Diagram.

The 4th, 7th and 10th holes in the floor sheets indicate the location of the leveling band posts. Attach with 5/16" x


1.1/4" bin bolts (S-277). In the 4th & 7th hole there will be 10 posts (1 at every 3rd sheet). In the 10th hole there will be 6 posts 1 every 5th.



### 36' LEVELING BAND POST INSTALLATION


Install the leveling band posts on the floor as shown in Diagram.

The 3rd, 6th and 10th holes in the floor sheets indicate the location of the leveling band posts. Attach with 5/16" x 1.1/4" bin bolts (S-277). In the 3rd hole from the bottom of the floor sheets there will be 13 posts (12 at 1 every 2nd sheet and 1 at 3 sheets). In the 6th hole there will be 9 posts (1 at every 3rd sheet). In the 10th hole there will be 5 posts (3 at 1 every 5th sheet and 2 at 1 every 6th sheet).



## LEVELING BAND INSTALLATION



Note: Field cut rounded notches in the outer leveling band(s) where the two roof support channels hang from the roof ribs.



21' LEVELING BAND LOCATION

Position leveling bands as shown in the drawings below.

Use (2) 5/16" x 3/4" bin bolts to attach bands to posts. Also use 5/16" x 3/4" bin bolts to to join band sections.  
**Note that band sections connect to each other only at endmost holes until completing the circle where an overlap may occur.**




24' LEVELING BAND LOCATION

Position leveling bands as shown in the drawings below.


Use (2) 5/16" x 3/4" bin bolts to attach bands to posts. Also use 5/16" x 3/4" bin bolts to to join band sections. **Note that band sections connect to each other only at endmost holes until completing the circle where an overlap may occur.**

Inner Leveling Bands



3 Band Sections per Ring  
4 Bays w/15 Holes Between Posts  
and 1 Bay w/19 Holes Between Posts

Outer Leveling Bands




6 Band Sections per Ring  
7 Bays w/23 Holes Between Posts




**30' LEVELING BAND LOCATION**

**INNER LEVELING BANDS**



2 BAND SECTIONS / RINGS- 6 BAYS W/13 HOLES BETWEEN POSTS


**Middle Leveling Bands**



6 BAND SECTIONS / RINGS- 10 BAYS W/15 HOLES BETWEEN POSTS

**30' LEVELING BAND LOCATIONS**


**OUTER LEVELING BANDS**



**9 BAND SECTIONS / RING- 10 BAYS W / 24 HOLES BETWEEN POSTS**


### **36' LEVELING BAND LOCATIONS**

#### **INNER LEVELING BANDS**




5 BAND SECTIONS/RINGS- 6 BAYS W/20 HOLES BETWEEN POSTS

#### **NO. 2 SET OF LEVELING BANDS**




7 BAND SECTIONS/RINGS- 12 BAYS W/15 HOLES BETWEEN POSTS

**36' LEVELING BAND LOCATION**  
**NO. 3 SET OF LEVELING BANDS**



10 BAND SECTIONS/RINGS- 12 BAYS W/22 HOLES BETWEEN POSTS

**NO. 4 SET OF LEVELING BANDS**



13 BAND SECTIONS/RINGS- 18 BAYS W/18 HOLES BETWEEN POSTS

### Auto-Vent Assembly & Installation Instructions

The following instructions are for assembling and installing the Auto-Vent. First, check the packing list to ensure all components have been shipped. The unit is easiest assembled in the **upside down position** as shown in the instructions. Roof vent location should be as shown on the following page.

#### Assembly

1. Take all parts out of the shipping box and check if all parts are present.
2. Turn one (1) roof vent housing (MIS-6778) upside down. (See Figure #1)
3. Insert 5/16" x 1.1/4" bin bolt with neoprene washer through hole in the side of roof vent. Place jamb nut onto the bolt and tighten. (See Figure #1)
4. Slide flap assembly (MIS-6777) onto bolt. The bolt should slide through hole in the flap assembly bracket. Install with curvature cupped upward and the brackets in the position as shown.
5. Insert 5/16" x 1.1/4" bin bolt with neoprene washer through the other side of the roof vent, through jamb nut and other flap assembly bracket. Tighten nut against vent housing side.
7. Place hold-down angle (MIS-4404) on the assembled roof vent. The wide end of the hold-down angle must face vent discharge. Once aligned, screw nine (9) #10 self-drilling (S-280) screws through the roof housing and into the holddown angle. (See Figure #2).




Figure #1





Figure #2

## Auto-Vent Assembly & Installation Instructions


### Installation

8. If the roof sheet does not have a prepunched hole for the roof vent, a hole must be cut. The cut hole should match the roof vent. The hole's inside edge should be approximately fifteen (15) inches from the eave. (See Figure #5)

9. Place the three (3) foam strips on roof sheet, as shown in Figure #4. Position roof vent over foam strips and bolt down using 5/16" x 3/4" bin bolts and nuts. (Note: See instructions below for lower two (2) bolts of vent).




**FIGURE #3**



**FIGURE #4**


5/16" x 3/4" Nuts & Bolts  
(12 Required)  
**Caulk with tube caulking**  
(Three sides of vent housing)



Foam Strips  
(1)Top (MIS-6780)  
(2)Sides (MIS-6781)

**FIGURE #5**

## Manway Cover Assembly




Apply caulking to underneath side of moisture diverter to seal between the corrugated roof sheet and diverter. Attach the moisture diverter and hinge base to manway roof sheet with 5/16" x 3/4" bolts and nuts. Place hinge leaf on manway cover and bolt both hinge parts together with 3/8" x 1" bolts and lock nuts. The handle is fastened on with two #10-24 x 5/8" long bolts and #10-24 lock nuts. Slip a 5/16" nut in the latch bar, thread on the shaft of handle, and adjust latch bar so it will catch the bottom side of the manway sheet. Snap the Manway Seal Strip to the manway seal.

## **TOP DRY ROOF ASSEMBLY**


For best results in erecting the roof, install two roof panels in four places as shown in Diagram A. When these eight panels are in place, your peak assembly should be centered. Next, add two or three panels at a time to each section making certain to lap them the same way, until all panels are in place. Be sure the panels are bolted loosely. **DO NOT TIGHTEN BOLTS UNTIL THE ROOF IS COMPLETELY ASSEMBLED.** When applying the roof panels, take into consideration the placement of the manway for ease of access to and from the sidewall and roof ladders.

**Fasten Roof Sheets To Eave Clips And Sidewall Sheets As You Assemble.**



### **ROOF OVERLAY**

NOTE: USE THE SAME OVERLAY PROCEDURE  
ON ALL ROOF SHEETS.



**DIAGRAM A**



### ROOF ASSEMBLY SPECIAL INSTRUCTIONS

SEE ROOF INSTALLATION MANUAL LOCATED WITH ROOF HARDWARE PACKAGE.

1. Do not use the Eave Clips that are located in the Roof Hardware Package. Use TD-101017 Eave clips for 21'-24' tanks, and TD-101074 Eave Clips for 30'-36' tanks. The Top Dry Eave Clips are located in the TDC-"Diameter"C Crate.
2. Locate eave clips so that a roof sheet will be centered over sidewall ladder.
3. Use TD-100274 Roof Brackets shipped in the Top Dry hardware rather than the brackets shipped in the roof hardware.

TD-101074  
Small Eave Clip  
TD-101017  
Large Eave Clip



## Roof Assembly For 21' Thru 24' Bins

**NOTE:** Be sure to install ladder rungs and safety steps as you assemble roof panels. When assembling such pieces as roof ladder rungs, remove the neoprene washer from bolt and place between the roof and the piece you are adding. This will insure a more protective seal against moisture.

### CENTER COLLAR

CRP-4609 (3) 21' ROOF - BLUE  
CRP-4608 (3), 24' ROOF - RED

5/16" X 3/4" BOLTS & NUTS

**TYPICAL ALL EAVE CLIPS**  
5/16" X 3/4" BIN BOLT, NUT AND WASHER

\* Leave out top row of bolts along top edge of rib for collar flashing, to installed later.

APPLY A BEAD OF CAULKING  
AROUND THE CENTER COLLAR

5/16" X 1.1/4" BOLTS & NUTS

### TYPICAL ROOF DETAILS

ROOF CHANNELS,  
2 REQUIRED UNDER ROOF  
LADDER RIBS. POSITION  
CHANNEL AS CLOSE TO EAVE  
AS POSSIBLE.  
CRP-4693 21' & 24'  
ROOF CHANNEL

### IMPORTANT:

START ROOF CHANNEL 2nd  
HOLE FROM THE BOTTOM OF  
ROOF RIB

ROOF STEP

TD-101074 EAVE  
CLIP


TD-100274  
INTERMEDIATE EAVE CLIP

5/16" X 3/4" BOLTS & NUTS

**NOTE:** Use Top Dry Intermediate  
Eave Clip, and Eave Clip located in  
TDC-(tank Dia.)C parts crate.


## 21" Thru 24' Roofs (Continuation)

To assemble slide rods and cover, insert straight end of slide rod through the center collar and thread one 5/16" nut all the way down on the rod, followed with a washer. Then place rod through the cover and put a washer and nut on the outside. **DO NOT TIGHTEN!** Put a nut on the bent end of the rod, followed with a washer. Insert rod through the cover, then place washer and nut on the outside. **TIGHTEN!** Adjust and tighten nuts on straight end of rod. After tightening, it may be necessary to spread the rods slightly to make them parallel. (Maintain 10" between rods.)



**SECTION THRU CENTER COLLAR**

- CRP-4618 (3) 12' ROOF FLASHING  
CRP-4619 (3) 15' ROOF FLASHING  
CRP-4620 (3) 18' ROOF FLASHING  
CRP-4621 (3) 21' ROOF FLASHING  
CRP-4622 (3) 24' ROOF FLASHING



**TOP VIEW**


## Roof Assembly For 30' Bins

**NOTE:** Be sure to install ladder rungs and safety steps as you assemble roof panels. When assembling such pieces as roof ladder rungs, remove the neoprene washer from bolt and place between the roof and the piece you are adding. This will insure a more protective seal against moisture.

### CENTER COLLAR

CRP-4608 (3) 30' ROOF - RED

5/16" X 3/4" BOLTS & NUTS



**TYPICAL ALL EAVE CLIPS**  
5/16" X 3/4" BIN BOLT, NUT AND WASHER

\* Leave out top row of bolts along top edge of rib for collar flashing, to installed later.

APPLY A BEAD OF CAULKING  
AROUND THE CENTER COLLAR

5/16" X 1 1/4" BOLTS & NUTS

### TYPICAL ROOF DETAILS

ROOF CHANNELS,  
2 REQUIRED UNDER ROOF  
LADDER RIBS. POSITION  
CHANNEL AS CLOSE TO EAVE  
AS POSSIBLE.  
CRP-4692 30'  
ROOF CHANNEL

### IMPORTANT:

START ROOF CHANNEL 2nd  
HOLE FROM THE BOTTOM OF  
ROOF RIB

ROOF STEP

TD-101017 EAVE  
CLIP

TD-100274  
INTERMEDIATE EAVE CLIP



5/16" X 3/4" BOLTS & NUTS

**NOTE:** Use Top Dry Intermediate  
Eave Clip, and Eave Clip located in  
TDC-(tank Dia.)C parts crate.

## 30' Roofs (Continuation)

**NOTE: See previous pages for assembling the peak cap and slide rods**


Prior to assembly of roof and center collar, you will need to position the flashing so the cap hold down is in line with roof ladder. Two holes per flashing section has been provided for the hold down bracket. Preassemble center collar and flashing pieces together before attaching roof panels to flashing. **TIGHTEN BOLTS, EXCEPT FOR THE 2 LOWER FLASHING SEAM BOLTS!**



## FLASHING DETAIL

### 30' Roofs (Continuation)


After all roof panels have been attached to the roof flashing, slip the roof panel seal clip between the bottom surface of the flashing and the top of the roof ribs. Be sure to push the clip in as far as possible for the best seal. Tighten all bolts and nuts after clips are pushed in.





## 36' Roofs (Continuation)

### IMPORTANT



For proper center collar flashing assembly, you must start the flashing seam directly above the center "Z" collar seam.

Improper placement will result in holes and notches not aligned properly.




### 36' Roofs (Continuation)

**NOTE:** See previous pages for assembling the peak cap and slide rods.

**INTERMEDIATE CENTER COLLAR**  
CRP-4687 (3) 36' ROOF (GREEN)


**NOTE:** INSTALL FLASHING AFTER ROOF  
PANELS HAVE BEEN PLACED



Be sure to install ladder rungs and safety steps as you assemble roof panels (see drawing below). At this point you will have completed assembly of the roof. Do not tighten bolts yet. Optional equipment and accessories should now be installed.

**NOTE:** *When assembling such pieces as roof ladder rungs, remove neoprene washer from bolt and place between the roof and the piece you are adding. This will insure a more protective seal against moisture.*

**IMPORTANT:** Maximum weight to be supported and/or suspended from the roof is to be 2,500 pounds for 21' thru 36' (non-trussed) ONLY.



### SAFETY RING INSTALLATION

To determine the location of the safety rings, start at the narrow or peak of the roof panel and count each hole separately. Having counted down the required distance, install the appropriate brackets. See chart below for proper location.


Expansion bolts should be fully contracted when assembling safety rings. When you have completely assembled both rings, (but before expanding) tighten all roof bolts including eave clip bolts. Now extend expansion bolts by running nut out on threads. This procedure should be continued evenly around the roof until the ring raises the roof to show a slight crown.

**SAFETY SUGGESTION:** It is possible for safety and bridging ring Expansion Bolts to become dislodged from the ring during high winds or when the inside pressure of your bin is too great. If one Expansion Bolt is dislodged, the entire ring will become useless. To remedy this situation, holes must be drilled through the safety ring and Expansion Bolts after the rings have been installed and expanded to the correct size. A cotter pin or bolt should then be inserted through each hole.

**NOTE:** *Welding of Expansion Nuts to the pipe and Expansion Bolt may be done as an option to drilling and pinning.*

### 21 FT - 36 FT. DIA. TANKS

BIN DIA.	SAFETY RING LOCATION FROM CENTER	SAFETY RING COLOR CODE	PART NUMBER	COMPLETE SAFETY RING	HARDWARE
21 FT.	5th HOLE	RED/WHITE	CRP-5363-24	CRP-4703	PLS-40227
24 FT.	5th HOLE	RED/WHITE	CRP-5363-24	CRP-4704	PLS-40228
30 FT.	8th HOLE	LIGHT BLUE	CRP-5363-30	CRP-4706	PLS-40230
36 FT.	7th HOLE	GOLD	CRP-5363-36	CRP-4719	PLS-40232




***NOTE: Last safety ring/bridging ring pipe will need to be cut to length.***

PERFORATED CENTER BAND

Drill 3/8" diameter holes equally spaced as shown in chart for top band clips. Attach clips using 5/16" x 3/4" bin bolts. Add perforated band sections. Note that these do not attach to the leveling bands but hang down on the inside of the top inner leveling band.

NOMINAL DIA. OF TANK (FT.)	NUMBER OF HOLES	DIMENSION
21'	6	25 1/4"
24'	6	25 1/4"
30'	6	22"
36'	12	34"




NOMINAL DIA. OF TANK (FT.)	PART NUMBER "A"	QUANTITY REQUIRED
21'	TD-100219	3
24'	TD-100219	3
30'	TD-100545	6
36'	TD-100726	6

## 42" FAN DIFFUSER INSTRUCTIONS & INSTALLATION

Bolt the long side of the hangers to the endmost slots of the top plate (TD-100665) as shown below.

Hold the top plate up under the bottom flange of the "C" channel in front of the fan opening. Mark and drill four 3/8" holes into bottom flange using diffuser hangers as a guide. Using 5/16" x 3/8" bolts and nuts bolt the top plate to the "C" channel.




### 42" FAN DIFFUSER (CONT.)

Attach front plate to the top plate with four (4) 1/4" x 1" self-drilling screws.

Bolt the side brackets to the front plate slot with the angle outward. field drill two (2) holes (on inside corrugation hills) through the sidewall and install 5/16" x 3/4" bin bolts and nuts.


Position the side plates on each side with the angle outward and fasten in place using six (6) 1/4" x 1" self-drilling screws.

**NOTE: The corner bolt will need to be removed through the side plate, side bracket and front plate.**




FAN ENTRANCE SHEETS

24" thru 36" Fans




42" Fans





Detailed Layout For Proper Location Of Platforms




## ACCESS DOOR PLATFORM TDP-5012

Before assembly of any platform, read the entire instructions to assure proper placement and assembly.

Refer to Figure #46 for proper location of access door platform. Begin by assembling the access door platform support frame using 5/16" x 3/4" truss head bolts and nuts. When attaching platform vertical support to bin sidewall field drill (16) 3/8" diameter holes for each support spaced every 4". Be sure and use 5/16" x 3/4" bin bolt on vertical support to sidewall. Special attention should be taken when assembling the platform support that the support brace is placed correctly.

Now proceed to the platform floor. Align holes on platform floor with holes on platform support and bolt together using 5/16" x 3/4" truss head bolt and nuts. Next, assemble handrail posts, handrails, and handrail braces.



Key	Part No.	Description	Quantity	Weight
1	LS-371	Platform Vertical Angle 42"	3	11.38
2	TDP-5000	Handrail 59"	2	10.15
3	TDP-5002	Handrail 30"	2	10.15
4	TDP-5003	Handrail Brace 36.29/32"	2	6.34
5	TDP-5005	Floor Brace 58.1/2"	3	26.11
6	TDP-5006	Platform Floor 37.7/8"	2	38.23
7	TDP-5007	Support Brace 50.21/32"	2	15.08
8	TDP-5008	Sidewall Brace 58"	2	19.65
9	TDP-5009	Platform Support 43.1/2"	2	12.95
10	TDP-5010	Platform Floor Splice 37.1/2"	1	6.24
11	TDP-5011	Platform Toe Plate 29.3/4"	1	3.29
12	TDP-5014	Access Door Package Hardware	1	5.41
13	TDP-5008N	Sidewall Brace 2.66"	2	16.61


### SMALL PLATFORM ASSEMBLY

For 36" Fans and Smaller or  
with #1 fan when two 36" or smaller fans are installed

Before assembling any platform, read all of the instructions first to assure proper placement and assembly.

Refer to Figure #43 for proper location of small platform. Begin by assembling the small platform support frame using 3/8" x 1" bolts on all connections. Use 5/16" x 1.1/4" bin bolt to attach platform vertical supports to sidewall stiffeners.

Be sure and locate the 5/16" x 1.1/4" bolts from the inside of the bin to the outside. This will provide maximum weather protection.




**Small Platform**  
36" Fans and Smaller  
TD-100092

Key	Part No.	Description	Quantity	Weight
1	TD-100051	Channel Bracket	8	3.90
2	TD-100052	Handrail Post 49.3/4"	4	31.69
3	TD-100059	Long Toeboard 78.1/2"	2	10.96
4	TD-100060	Short Toeboard 54.1/2"	1	3.80
5	TD-100061	Long Handrail 78.1/2"	4	37.52
6	TD-100062	Short Handrail 54.1/2"	2	13.02
7	TD-100064	Floor Plank 78"	11	112.87
8	TD-100066	"X" Brace Strap 60"	4	7.26
9	TD-100067	Mid Channel Support 74"	2	32.73
10	TD-100070	Side Channel Support 78.1/2"	2	41.26
11	TD-100072	End Channel Support 78.1/2"	2	41.60
12	TD-100686	Vertical Support 70"	2	43.11
13	TD-100083	Support Channel 80.7/8"	2	32.98
14	TD-100084	Knee Brace 83.5/8"	2	23.67
15	TD-100090	Small Platform Hardware Package	1	8.96


## SMALL PLATFORM ASSEMBLY

(CONT.)

36" Fans and Smaller  
TD-100092



Position the vertical support to the existing sidewall stiffeners as shown in Figure #46 and double nut with 5/16" nuts.




When bolting stiffener to sidewall at locations where platform supports are to be attached, use (25) 5/16" x 1.1/4" bin bolts, heads to inside. Start 12 inches below horizontal seam of second and third rings from top. See Figure #46.

## LARGE PLATFORM ASSEMBLY For 42" Fan


Before assembly of any platform, read the entire instructions to assure proper placement and assembly.

Refer to Figure #43 for proper location of large platform. Begin by assembling the large platform support frame using 7/16" x 1" bolts on all connections. Use 5/16" x 1.1/4" bin bolt to attach the platform vertical supports to the sidewall stiffeners. Be sure and place the 5/16" x 1.1/4" bolts from the inside of the bin to the outside. This will provide maximum weather protection.




Key	Part No.	Description	Quantity	Weight
1	TD-100051	Channel Bracket	10	4.87
2	TD-100052	Handrail Post 49.3/4"	7	55.47
3	TD-100053	Toeboard 71.1/2"	1	4.99
4	TD-100054	Toeboard 92"	1	6.42
5	TD-100055	Toeboard 95.1/2"	1	6.67
6	TD-100056	Handrail 71.1/2"	2	17.07
7	TD-100057	Handrail 92"	2	22.98
8	TD-100058	Handrail 95.1/2"	2	22.81
9	TD-100063	Floor Plank 95.1/2"	13	163.35
10	TD-100065	"X" Brace Strap 94.5/16"	2	8.75
11	TD-100068	Mid Channel Support 88"	3	58.37
12	TD-100069	Side Channel Support 96"	2	50.46
13	TD-100071	End Channel Support 92.1/2"	2	49.15
14	TD-100085	Short Knee Brace 72.9/32"	2	54.51
15	TD-100086	Support Channel 98.3/8"	2	53.08
16	TD-100087	Long Knee Brace 114"	2	85.98
17	TD-100685	Vertical Support 94"	2	63.64
18	TD-100091	Large Platform Hardware Package	1	14.35

# **LARGE PLATFORM ASSEMBLY** (CONT.) (FOR 1 FAN SYSTEMS OR #2 FAN ON 2 FAN SYSTEMS)



Position the vertical support to the existing sidewall stiffeners as shown in Figure #46 and double nut with 5/16" nuts.




When bolting stiffener to sidewall at locations where platform supports are to be attached, use (25) 5/16" x 1.1/4" bin bolts, heads to inside. Start 12 inches below horizontal seam of second and third rings from top. See Figure #46.

### CROSS OVER PLATFORM ASSEMBLY (For use with stairs) TDP-5013

Before assembly of any platform, read the entire instructions to assure proper placement and assembly.

Refer to Figure #46 for proper location of cross over platform. Begin by assembling the cross over platform support frame using 5/16" x 3/4" truss head bolts and nuts. When attaching platform vertical support to bin sidewall field drill (16) 3/8" diameter holes for each support spaced every 4". Be sure and use 5/16" x 3/4" bin bolt on vertical support to sidewall. Special attention should be taken when assembling the platform support that the support brace is placed correctly.

Now proceed to the platform floor. Align holes on platform floor with holes on platform support and bolt together using 5/16" x 3/4" truss head bolt and nuts. Next, assemble handrail posts, handrails, and handrail braces.



Key	Part No.	Description	Quantity	Weight
1	LS-371	Platform Vertical Angle	2	7.59
2	TDP-5001	Handrail 27"	2	4.63
3	TDP-5003	Handrail Brace 36.29/32"	2	6.34
4	TDP-5004	Short Floor Brace 26.1/2"	3	11.85
5	TDP-5006	Platform Floor 37.7/8"	1	19.11
6	TDP-5007	Support Brace 50.21/32"	2	15.08
7	TDP-5008	Sidewall Brace 58"	2	19.65
8	TDP-5009	Platform Support 43.1/2"	2	12.95
	TDP-5015	Cross Over Plat. Hdw. Pack.	1	3.95


## TRANSITION INSTALLATION (TR-4734)

BEFORE CUTTING THE OPENING CHECK THAT TR-4734 IS THE TRANSITION THAT WAS ORDERED.

When installing the GSI aeration transition, it will be necessary to field cut a hole into the bottom sidewall ring (usually straight across from the unload auger). Refer to diagram for proper dimensions of cutout. The base angle will also need to be cut at entrance collar cutout. Take note of the diagram showing the 1" dimension from bottom of entrance collar side bracket to concrete. This is important for proper fit of transition.

**NOTE:** Entrance collar side bracket must be bolted on the inside of the bin sidewall.


### AS VIEWED FROM INSIDE BIN



Part No.	Description	Quantity
S-275	5/16" - 18 3/4" Bin Bolt Grade 5	125
S-280	#10 - 16 x 5/8" Self Drill Screw	10
S-3651	Tube Caulk - Gray Butyl #506-15	1
S-396	5/16" - 18 Hex Nut Grade 2	125
S-7264	Spec Neoprene Seal Strip W/ADH	10 Ft



TRANSITION ASSEMBLY (TR-4734)



- 
- This exploded view diagram illustrates the assembly of a three-door refrigerator. The components are numbered 1 through 5, corresponding to the parts list. The diagram shows the front panels (1), the internal frame (2), the middle shelves (3), and the bottom panels (4). The assembly is shown in a disassembled state to illustrate the relationship between the parts. Key components and their part numbers are labeled:
- 1**: Front panel (left and right doors)
  - 2**: Internal frame (middle and side panels)
  - 3**: Middle shelves
  - 4**: Bottom panels (left and right doors)
  - 5**: Bottom panel (middle door)
- Other labeled parts include:
- S-3611: Hinge pin
  - S-6005: Screw
  - S-5220: Screw
  - S-945: Screw
  - TD-101021: Hinge pin
  - TD-101022: Hinge pin
  - KCD-4513: Hinge pin
  - S-7004: Hinge pin
  - S-385: Hinge pin
  - D02-0005, D03-0512, S-786: Hinge pin

## Top Dry Autoflow


---

Key	Part #	Description	Qty.
1	TD-100990	Access Door Plate	1
2	TD-100991	Access Top/Bottom Z-Frames	4
3	TD-100992	Access Door Side Z-Frames	4
4	TD-100993	Top Access Door	2
5	TD-100994	Inside Access Door	2
x	TD-101020	Rear Door Catches	2
x	TD-101021	Outside Door Latches	2
x	TD-101020	Inside Door Latches	2
x	D03-0512	Lockable Handle	2
x	D02-0045	Gasket for Lockable Handle	2
x	ACD-4513	Access Door Handle w/Gasket	2

## TWO RING DOOR INSTALLATION & ACCESSORIES


Before starting to install, be sure the correct door has been received.

### 4.00" Bin Corrugation WD-6133 21' Bins



- 1.) Remove inner door panels, and outer door cover. Apply double row of rope caulk along door flanges, noting how door and bin sheets lap. The top of the door frame goes to the inside of the sidewall and the bottom of the door frame goes to the outside of the sidewall sheet. With inner door panels and outer door cover removed set door frame into opening. **Insert a bolt at the (4) corners of door frame and sidewall, do not tighten until completing step #2.**
- 2.) Reinstall inner door panels at original locations. Close latch bars to lock panels in place. Be sure that panels are fully seated over all bearing pins. Install inner panel hinge assemblies per illustration instructions with hinges. **Note: do not distort door frame with use of alignment or drift punches - if necessary, drill or ream holes to insert bolts in door frame. Now tighten frame bolts starting at center and working toward top and bottom on each side.**
- 3.) Keep inner panels latched and loosen all bearing pin bolts. Retighten all bearing pin bolts. This makes loading on pins uniform for easier operation of panels.
- 4.) If some latch bars are loose or require excessive force to lock, loosen hex socket capscrews and adjust in or out until latch bars operate smoothly. Check that the panels are fully seated over all bearing pins.
- 5.) Re-install outer cover. Adjust outer door hinges and latches as required.
- 6.) Assemble door hold back as shown on next page. Open door cover until it approaches the bin wall. Hook retaining bracket over lower latch mount and position the door hold back against bin wall in a valley. Drill a 3/8" hole through the bin wall and bolt the door hold back to the bin.


2-RING DOOR ASSEMBLY




## PARTS LIST FOR 2-RING DOORS

KEY	DESCRIPTION	PART NUMBER		PART NUMBER		QUANTITY		QUANTITY
		12'-27" BIN DIA.	4.00" CORR.	30'-60" BIN DIA.	4.00" CORR.	12'-27" BIN DIA.	4.00" CORR.	
1	OUTER DOOR COVER	WD-039		WD-039		1		1
2	OUTER COVER LATCH BRACKET	WD-2854		WD-2854		2		2
3	OUTER COVER HINGE BRACKET	WD-225		WD-225		2		2
4	DOOR COVER BRACE SECTION	WD-035		WD-035		4		4
5	DOOR RETAINER	WD-033		WD-033		3		3
6	OUTER COVER LATCH MOUNT BASE	WD-6124		WD-6124		2		2
7	OUTER COVER HINGE BASE	WD-6066		WD-6066		2		2
8	BOTTOM INNER DOOR HINGE	WD-6055		WD-6055		1		1
9	MIDDLE INNER DOOR HINGE	WD-6056		WD-6056		2		2
10	TOP INNER DOOR HINGE	WD-6054		WD-6054		1		1
11	RUBBER TRIM SEAL STRIP	S-4380		S-4380		2.1/4 FT.		2.1/4 FT.
12	LATCH BAR	WD-6039		WD-6039		3		3
13	INNER PANEL LATCH - RIGHT HAND	WD-6037		WD-6037		3		3
14	INNER PANEL LATCH - LEFT HAND	WD-6038		WD-6038		3		3
15	1/2" X 1" HEX SOCKET CAPSCREW	S-7160		S-7160		6		6
16	LATCH BUSHING	WD-6040		WD-6040		6		6
17	LONG BEARING PIN	WD-6079		WD-6079		38		38
18	INNER PANEL REINFORCING ANGLE	WD-6125		WD-6125		6		6
19	BOTTOM INNER DOOR PANEL	WD-6128		WD-6128		1		1
20	MIDDLE INNER DOOR PANEL	WD-6127		WD-6127		1		1
21	TOP INNER DOOR PANEL	WD-6126		WD-6126		1		1
22	BOTTOM INNER DOOR PORT HOLE COVER	WD-6028		WD-6028		1		1
23	INNER DOOR HINGE STRAP	WD-6053		WD-6053		6		6
24	DOOR HOLD BACK BRACKET	WD-1302		WD-1302		1		1
25	DOOR HOLD BACK EXTENSION	WD-6110		WD-6110		1		1

**OPTIONAL BIN STEP ASSEMBLY**  
**WD-042**




Field drill holes in sidewall  
sheet on ridge of corrugation.




## BASE ANGLE

Once the door frame has been placed and secured, continue adding necessary sidewall ring(s). To the lower edge of the bottom ring, attach the base angle ring. Before lowering the bin, apply mastic sealer to the entire underneath side of the base angle. (See below.) Next, lower the bin onto the foundation and check for an adequate seal.



## BASE STIFFENER SHIM



**Figure #63**





**WARRANTY**

THE GSI GROUP, INC. ("GSI") WARRANTS ALL PRODUCTS MANUFACTURED BY GSI TO BE FREE OF DEFECTS IN MATERIAL AND WORKMANSHIP UNDER NORMAL USAGE AND CONDITIONS FOR A PERIOD OF 12 MONTHS AFTER RETAIL SALE TO THE ORIGINAL END USER OF SUCH PRODUCTS. GSI'S ONLY OBLIGATION IS, AND PURCHASER'S SOLE REMEDY SHALL BE FOR GSI, TO REPAIR OR REPLACE, AT GSI'S OPTION AND EXPENSE, PRODUCTS THAT, IN GSI'S SOLE JUDGMENT, CONTAIN A MATERIAL DEFECT DUE TO MATERIALS OR WORKMANSHIP. ALL DELIVERY AND SHIPMENT CHARGES TO AND FROM GSI'S FACTORY WILL BE PURCHASER'S RESPONSIBILITY. EXPENSES INCURRED BY OR ON BEHALF OF THE PURCHASER WITHOUT PRIOR WRITTEN AUTHORIZATION FROM AN AUTHORIZED EMPLOYEE OF GSI SHALL BE THE SOLE RESPONSIBILITY OF THE PURCHASER.

EXCEPT FOR THE ABOVE STATED EXPRESS LIMITED WARRANTIES, GSI MAKES NO WARRANTY OF ANY KIND, EXPRESSED OR IMPLIED, INCLUDING, WITHOUT LIMITATION, WARRANTIES OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE OR USE IN CONNECTION WITH (i) PRODUCT MANUFACTURED OR SOLD BY GSI OR (ii) ANY ADVICE, INSTRUCTION, RECOMMENDATION OR SUGGESTION PROVIDED BY AN AGENT, REPRESENTATIVE OR EMPLOYEE OF GSI REGARDING OR RELATED TO THE CONFIGURATION, INSTALLATION, LAYOUT, SUITABILITY FOR A PARTICULAR PURPOSE, OR DESIGN OF SUCH PRODUCT OR PRODUCTS.

IN NO EVENT SHALL GSI BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL OR CONSEQUENTIAL DAMAGES, INCLUDING, WITHOUT LIMITATION, LOSS OF ANTICIPATED PROFITS OR BENEFITS. PURCHASER'S SOLE AND EXCLUSIVE REMEDY SHALL BE LIMITED TO THAT STATED ABOVE, WHICH SHALL NOT EXCEED THE AMOUNT PAID FOR THE PRODUCT PURCHASED. THIS WARRANTY IS NOT TRANSFERABLE AND APPLIES ONLY TO THE ORIGINAL PURCHASER. GSI SHALL HAVE NO OBLIGATION OR RESPONSIBILITY FOR ANY REPRESENTATIVE OR WARRANTIES MADE BY OR ON BEHALF OF ANY DEALER, AGENT OR DISTRIBUTOR OF GSI.

GSI ASSUMES NO RESPONSIBILITY FOR FIELD MODIFICATIONS OR ERECTION DEFECTS WHICH CREATE STRUCTURAL OR STORAGE QUALITY PROBLEMS. MODIFICATIONS TO THE PRODUCT NOT SPECIFICALLY COVERED BY THE CONTENTS OF THIS MANUAL WILL NULLIFY ANY PRODUCT WARRANTY THAT MIGHT HAVE BEEN OTHERWISE AVAILABLE.

THE FOREGOING WARRANTY SHALL NOT COVER PRODUCTS OR PARTS WHICH HAVE BEEN DAMAGED BY NEGLIGENT USE, MISUSE, ALTERATION OR ACCIDENT. THIS WARRANTY COVERS ONLY PRODUCTS MANUFACTURED BY GSI. THIS WARRANTY IS EXCLUSIVE AND IN LIEU OF ALL OTHER WARRANTIES EXPRESS OR IMPLIED. GSI RESERVES THE RIGHT TO MAKE DESIGN OR SPECIFICATION CHANGES AT ANY TIME.

PRIOR TO INSTALLATION, PURCHASER HAS THE RESPONSIBILITY TO RESEARCH AND COMPLY WITH ALL FEDERAL, STATE AND LOCAL CODES WHICH MAY APPLY TO THE LOCATION AND INSTALLATION.



a division of

THE GSI GROUP



**1004 East Illinois Street  
Assumption Illinois 62510  
(217)-226-4421**